

KINGS STERNDALE

LOCATION: Kings Sterndale

PROJECT: Sympathetic Restoration – Phases 1, 2, & 3

PROJECT LENGTH: 28 Weeks

INFORMATION: Restoration Projects were contracted to carry out the structural restoration and refurbishment works at Christ Church King Sterndale. The church was in need of urgent structural repairs, bulging walls and buttresses were numbered and photographed. Stonework was carefully dismantled and re-built using 3.5 hydraulic lime graded yellow sand and limestone dust mix., in accordance with our English Heritage specification. Works Included:

- Structural ties
- Re-building the nave west wall and adjoining buttresses.
- Structural repairs to the chancel north wall.
- General re-pointing
- Re-building of the bell tower
- Roof repairs & replacement of perished stone slates
- Replacement of perished masonry, carved to match
- Restoration of bell and pulley
- New English oak & code 6 lead window hoods

“Very impressed by the care and interest taken, the work completed has been of a high standard. I will be happy if future clients of Restoration Projects wish to visit the church to see the fine workmanship for themselves” Rev Don Sparkes, Christ Church King Sterndale.

